



NOTES :

1. ALL WORK TO BE DONE AND ALL MATERIALS SUPPLIED SHALL CONFORM TO THE STATE OF CALIFORNIA, DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS. (LATEST EDITION)
2. CONCRETE SHALL BE CLASS A - SIX (6) SACKS OF CEMENT PER CUBIC YARD.
3. AN 8" FLOW LINE SHALL BE LEFT SMOOTH TROWELED.
4. ALL BROOMING SHALL BE PARALLEL TO THE DIRECTION OF FLOW.
5. WHEN ROLLED CURB IS USED THERE SHALL BE A TRANSITION INSTALLED, 12 FEET BEYOND THE ENDS OF THE CURB RETURNS.
6. VERTICAL CURB TO BE USED AT ALL CURB RETURNS.
7. EXPANSION JOINT AT MID-POINT AND EACH END OF CROSS GUTTER, NOT TO EXCEED 15 FEET, (4.58 m), CENTERS OR AS DIRECTED BY ENGINEER.
8. NO STANDING WATER SHALL BE ALLOWED THRU THE LENGTH OF THE CROSS GUTTER AND APRONS. AGGREGATE BASE TO BE PLACED BELOW APRON AND CROSS GUTTER SECTIONS TO A DEPTH AS DESIGNATED BY THE COUNTY ENGINEER. IN NO EVENT SHALL IT BE LESS THAN 6" IN DEPTH.
- 9.

COUNTY OF GLENN — SUBDIVISION STANDARDS

**STANDARD VALLEY GUTTER
(NO SCALE)**

REV. DATE	DRG. NO.